

Q.P. Code : 733801

(CBGS)

(3 HOURS)

[Total Marks: 80]

N.B: 1) Question No:1 is compulsory.

2) Attempt any three questions out of remaining five questions.

3) Figures to the right indicates full marks

Q 1. Write short notes on any four of the following

- Work breakdown Structure
- Types of construction Projects
- Causes of accidents
- Quality Assurance
- Function of Material Management

Q 2.a Explain the 14 principles of management. 10

b Following table shows the activities, their interdependence and the duration. 10

Activity	A	B	C	D	E	F	G	H	K	M
Preceding activity	-	-	-	A	B	B	C	C	F, G	H, K, L
Duration (days)	3	3	3	18	4	15	8	11	7	5

- Draw a A-O-A network
- Work out all activity times and floats
- Identify the critical path and the project duration

3.a Explain in brief the phases in the life cycle of a construction project. 10

b For a small project, prepare a resource histogram based on EST and LST schedule. Comment on the suitability of distribution on above methods. 10

Activity	A	B	C	D	E	F	G
Preceding activity	-	-	-	A	B	C	E
Duration (days)	4	5	3	4	5	3	7
Masons required	3	4	4	3	2	4	8

Smoothen the resources depending upon the peak demands.

4.a Find out the optimum cost and optimum duration for this project. The indirect cost of the project is Rs. 3000/week 12

Activity	Immediate predecessor	Normal duration (weeks)	Normal Cost (Rs)	Crash duration (weeks)	Crash cost (Rs)
A	-	3	3000	1	4500
B	A	2	5000	1	8000
C	B	4	2000	2	4000
D	B	3	7000	1	10,000
E	B	2	12,500	2	12,500
F	C	3	10,000	1	13,000
G	D, E	5	6500	3	9000
H	F	4	4300	2	8000

[TURN OVER]

b What are the time overruns and cost overruns of a project? What are the methods to avoid them?

8
10

5.a The activity details of a small network is shown in the table below:

Activity	1-2	1-3	1-4	2-5	3-6	4-5	4-6	4-7	5-7	6-7
Time required	6	7	4	Dummy activity	4	12	10	8	5	6

The following conditions exist at the end of 10 days:

- i) Activity 1-2, 1-3 and 1-4 have been completed as originally scheduled.
- ii) Activity 4-5 is in progress and will require 6 more days for its completion.
- iii) Activity 4-6 is in progress and still require 6 more days for its completion
- iv) Activity 3-6 is in progress and will be completed in one day.
- v) Other activities have not been commenced and their original predicted duration will hold good, except for activity 5-7 which will require only three days instead of 5 days originally planned.

Update the network and determine the critical path of the updated network. What is the total increase in the project duration?

b Write short notes on:

10

- i) Statistical Quality Control
- ii) Resource Levelling
- iii) Cost Slope

6.a A small project is composed of seven activities as given below:

10

Activity		Estimated duration (weeks)		
i	j	t_0	t_m	t_p
1	2	2	3	5
1	3	4	9	14
1	4	2	8	12
2	5	1	1	1
3	5	2	5	14
4	6	2	8	10
5	6	3	9	15

- i) Draw project network
- ii) Find expected duration, standard deviation and variance of all activities.
- iii) Calculate the variance of the project duration.
- iv) What is the probability that the project will be completed 3 weeks earlier than the expected date?

b. Write short notes on any four of the following:

10

- i) Beta distribution curve
- ii) ISO 14000
- iii) OSHA
- iv) Requirements for preparation of a site layout
- v) Sources of funds for starting a project.

MUPD16025 ANJUMAN-ISLAMIA SKI TECHNICAL CAMPUS, COLLEGE OF ENGINEERING, PANVEL 24-05-2016 09:37:48